


CARGILL MEAT SOLUTIONS NEW TRUCK AREA & BUILDING ADDITION

LEXINGTON COUNTY, SOUTH CAROLINA



LOCATION MAP
N.T.S.

PREPARED BY

HB Engineering

SITE DEVELOPMENT CONSULTANTS


720 OLD CHEROKEE ROAD
LEXINGTON, SOUTH CAROLINA 29072
803-957-7027

MAY 10, 2022

DRAWING INDEX

OVERALL SITE PLAN	C1
EXISTING CONDITIONS & DEMOLITION PLAN	C2
GRADING, DRAINAGE, AND EROSION CONTROL PLAN	C3
DRAINAGE PROFILES & DETAILS	C4
DRAINAGE DETAILS	C5


OWNER:	CARGILL MEAT SOLUTIONS CORPORATION 1964 OLD DUNBAR RD WEST COLUMBIA, SC 29172 PH: 803-858-1901
CONTACT:	CONTACT: XXXXXXXXX EMAIL: XXXXXXXXXXXXXm
TMS#:	006896-03-004
SITE ADDRESS:	1964 OLD DUNBAR RD
TOTAL AREA:	12.42 AC
DISTURBED AREA:	1.4 AC
USE:	INDUSTRIAL



81
Know what's below.
Call before you dig.

OWNER:	CARGILL MEAT SOLUTIONS CORPORATION 1964 OLD DUNBAR RD WEST COLUMBIA, SC 29172 PH: 803-888-1901 CONTACT: XXXXXXXXX EMAIL: XXXXXXXXXXXXXXXXm
CONTACT:	068896-03-004 1964 OLD DUNBAR RD 12.42 AC 1.4 AC. INDUSTRIAL

N/F
LGM PROPERTIES LLC.
TM# 006896-03-003
USE: WAREHOUSE



- NOTES**
- ALL ELEVATIONS ARE BASED ON MEAN SEA LEVEL DATUM.
 - THE CONTRACTOR SHALL NOTIFY THE ENGINEER PRIOR TO CONSTRUCTION OF ANY DISCREPANCIES BETWEEN THESE PLANS AND ACTUAL FIELD CONDITIONS.
 - THE CONTRACTOR SHALL NOTIFY THE UNDERGROUND UTILITY LOCATION SERVICE AT LEAST 72 HOURS PRIOR TO BEGINNING ANY EXCAVATION.
 - ALL AREAS DISTURBED BY CONSTRUCTION (NOT COVERED BY PAVEMENT, BUILDINGS OR OTHER STRUCTURES) SHALL BE FINE GRADED AND GRASSED IN ACCORDANCE WITH THE SPECIFICATIONS.
 - ALL SUITABLE EXCESS SOILS EXCLUDING TOP SOIL SHALL BE STOCKPILED AS DIRECTED BY THE ENGINEER AND COMPACTED IN 8" LAYERS TO 90% MAXIMUM DRY DENSITY.
 - TOP SOIL SHALL BE STOCKPILED SEPARATELY AS DIRECTED BY THE ENGINEER.
 - ALL AREAS OF STOCKPIILING SHALL HAVE POSITIVE DRAINAGE AND SHALL BE GRASSED PER SPECIFICATIONS.
 - ALL STORM DRAIN PIPING SHALL BE CLASS III UNLESS OTHERWISE NOTED.

SEDIMENT AND EROSION CONTROL NOTES:

- IF NECESSARY, SLOPES WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.
- STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW.
 - WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE.
 - WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.
- ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY (9) DAYS. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY OR INCORRECTLY INSTALLED, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN 48 HOURS OF IDENTIFICATION.
 - PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION, FILL COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.
 - ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
- THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO THE PAVED ROADWAY CONSTRUCTION AREAS. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.
- RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE AS WELL AS FOR INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH S.C. REG. 72-300 ET SEQ. AND SCDDM000000.
- TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR DIVERT SEDIMENT LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.
- ALL WATERS OF THE (WOS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CANNOT BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WOS. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WOS.
- LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES TO FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.
- A COPY OF THE SWPPP, INSPECTION RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.
- INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:1V OR GREATER) WHERE LAND-DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS.
- MINIMIZE SOIL COMPACTION AND, UNLESS INFEASIBLE, PRESERVE TOPSOIL.
- MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE.
- MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMPs (SEDIMENT BASIN, FILTER BAG, ETC.).
- THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED:
 - WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL.
 - WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS.
 - FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE, AND
 - SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING.
- AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY (9) DAYS AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
- IF EXISTING BMPs NEED TO BE MODIFIED OR IF ADDITIONAL BMPs ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND/OR SC's WATER QUALITY STANDARDS, IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE. IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE, THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPs MUST BE IMPLEMENTED AS SOON AS REASONABLY POSSIBLE.
- A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB 10 ACRES OR MORE THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT HAS APPROVED OTHERWISE.

LEXINGTON COUNTY SEEDING SCHEDULE

FROM MAY 1 - AUGUST 31	FROM SEPT. 1 - APRIL 30
1 LB. BROWNTOPMILLET	2 LBS. ANNUAL RYE GRASS
1 LB. HULLED BERMUDA	1/2 LB. HULLED BERMUDA
25 LBS. 10-10-10 FERTILIZER	1-1/2 LBS. UNHULLED BERMUDA
75 LBS. LIMESTONE	25 LBS. 10-10-10 FERTILIZER
	75 LBS. LIMESTONE

OR

1 LB. BROWNTOPMILLET	2 LBS. ANNUAL RYE GRASS
1 LB. HULLED BERMUDA	1/2 LB. HULLED BERMUDA
*2 LBS. BAHIA GRASS	*1 LB. UNHULLED BERMUDA
25 LBS. 10-10-10 FERTILIZER	25 LBS. 10-10-10 FERTILIZER
75 LBS. LIMESTONE	75 LBS. LIMESTONE

OR

2 LBS. BROWNTOPMILLET	1 LB. UNHULLED BERMUDA
*3 LBS. BAHIA GRASS	2 LBS. RYE GRASS OR
25 LBS. 10-10-10 FERTILIZER	2 LBS. GRASS RYE
75 LBS. LIMESTONE	*2 LBS. BAHIA GRASS
	25 LBS. 10-10-10 FERTILIZER
	75 LBS. LIMESTONE

OR

2 LBS. BROWNTOPMILLET	1 LB. UNHULLED BERMUDA
*3 LBS. BAHIA GRASS	2 LBS. RYE GRASS OR
25 LBS. 10-10-10 FERTILIZER	2 LBS. GRASS RYE
75 LBS. LIMESTONE	*2 LBS. BAHIA GRASS
	25 LBS. 10-10-10 FERTILIZER
	75 LBS. LIMESTONE

ALL QUANTITIES OF GRASS LISTED ABOVE ARE PER 1,000 SQUARE FEET

* AROUND OFFICE BUILDINGS AND WITHIN SUBDIVISIONS, USE 4 TO 6 OUNCES OF CENTPEDE GRASS IN LIEU OF BAHIA GRASS OR IN COMBINATION WITH BERMUDA GRASS.

** FOR SOILS WITH CLAY SUBSOIL. DO NOT PLANT IN SANDY SOILS.




RECOMMENDED TEMPORARY SEEDING SPECIFICATIONS

Species	lbs./ac	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec
Browntop	40												
Millet (Alone)	10												
Millet (Mix)	10												
Rye Grain (Alone)	56												
Rye Grain (Mix)	10												
Rye Grass (Alone)	50												
Rye Grass (Mix)	8												

FOR STEEP SLOPES/CUT SLOPES

Weeping Lovegrass (Alone)	4												
Weeping Lovegrass (Mix)	2												

CONSTRUCTION SEQUENCE



720 OLD CHEROKEE ROAD
LEXINGTON, SOUTH CAROLINA 29072
803-957-7027 FAX 877-728-0808

CARGILL MEAT SOLUTIONS
NEW TRUCK AREA & BUILDING ADDITION
LEXINGTON COUNTY
SOUTH CAROLINA





No.	Date	Revision

Sheet Title:
GRADING, DRAINAGE, AND EROSION CONTROL PLAN


Drawn by: TB
Designed by: TB
Checked by: TB
Scale: 1"=30'
Project No.: 22116
Date: 5/10/2022

C3


5 of 5



TEMPORARY CONCRETE WASHOUT
N.T.S.




RIP-RAP PIPE OUTLET DETAIL
NOT TO SCALE




- NOTES:
1. SILT FENCE TO EXTEND AROUND ENTIRE PERIMETER OF STOCKPILE, OR IF STOCKPILE AREA IS LOCATED ON/NEAR A SLOPE THE SILT FENCE IS TO EXTEND ALONG CONTOURS OF THE DOWN GRADIENT AREA.
 2. IF STOCKPILE IS TO REMAIN FOR MORE THAN 14 DAYS, TEMPORARY STABILIZATION MEASURES MUST BE IMPLEMENTED.
 3. SILT FENCE SHALL BE MAINTAINED UNTIL STOCKPILE AREA HAS EITHER BEEN REMOVE OR PERMANENTLY STABILIZED.
 4. THE KEY TO FUNCTIONAL TEMPORARY STOCKPILE AREAS IS WEEKLY INSPECTIONS, ROUTINE MAINTENANCE, AND REGULAR SEDIMENT REMOVAL.


TEMPORARY STOCKPILE DETAIL
N.T.S.



TEMPORARY GRAVEL CONSTRUCTION EXIT
NOT TO SCALE




TEMPORARY CATCH BASIN INLET PROTECTION (POST PAVING)
NOT TO SCALE





- NOTES:
1. SEDIMENT SHALL BE REMOVED AND TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO 1/2 THE DESIGN DEPTH OF THE TRAP. REMOVED SEDIMENT SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.
 2. THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN AND REPAIRS MADE AS NEEDED.
 3. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND WATER POLLUTION SHALL BE MINIMIZED.
 4. THE SEDIMENT TRAP SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE REMAINING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

TEMPORARY CATCH BASIN SEDIMENT TRAP
NOT TO SCALE



- Installation
Excavate a trench approximately 6-inches wide and 6-inches deep when placing fabric by hand. Place 12-inches of geotextile fabric into the 6-inch deep trench, extending the remaining 6-inches towards the upslope side of the trench. Backfill the trench with soil or gravel and compact. Bury 12-inches of fabric into the ground when pneumatically installing silt fence with a slicing method. Purchase fabric in continuous rolls and cut to the length of the barrier to avoid joints. When joints are necessary, wrapped the fabric together at a support post with both ends fastened to the post, with a 6-inch minimum overlap. Install posts to a minimum depth of 24-inches. Install posts a minimum of 1- to 2- inches above the fabric, with no more than 3-feet of the post above the ground. Space posts to maximum 6-foot centers. Attach fabric to wood posts using staples made of heavy-duty wire at least 1 1/2-inch long, spaced a maximum of 8-inches apart. Staple a 2-inch wide lath or the filter fabric to securely fasten it to the upslope side of wooden posts. Attach fabric to the steel posts using heavy-duty plastic ties that are evenly spaced and placed in a manner to prevent sagging or tearing of the fabric. In soil cases, ties should be offset in no less than 4 inches. Install the fabric a minimum of 24-inches above the ground. When necessary, the height of the fence above ground may be greater than 24-inches. In tidal areas, extra silt fence height may be required. The post height will be twice the exposed post height. Post spacing will remain the same and extra height fabric will be 4-, 5-, or 6-foot tall. Locate silt fence checks every 100 feet maximum and at low points. Install the fence perpendicular to the direction of flow and place the fence the proper distance from the toe of steep slopes to provide sediment storage and access for maintenance and cleanup.
- Inspection and Maintenance
Inspect every seven calendar days and within 24-hours after each rainfall event that produces 1/4-inch or more of precipitation. Check for sediment buildup and fence integrity. Check where runoff has eroded a channel beneath the fence, or where the fence has sagged or collapsed by fence overtopping. If the fence fabric tears, begins to decompose, or in any way becomes ineffective, replace the section of fence immediately. Remove sediment accumulated along the fence when it reaches 1/3 the height of the fence, especially if heavy rains are expected. Remove trapped sediment from the site or stabilize it on site. Remove silt fence within 30 days after final stabilization is achieved or after temporary best management practices (BMPs) are no longer needed. Permanently stabilize disturbed areas resulting from fence removal.

TEMPORARY SILT FENCE
NOT TO SCALE





HB Engineering
SITE DEVELOPMENT CONSULTANTS
720 OLD CHEROKEE ROAD
LEXINGTON, SOUTH CAROLINA 29072
803-957-7027 FAX 877-728-0808

**CARGILL MEAT SOLUTIONS
NEW TRUCK AREA & BUILDING ADDITION
LEXINGTON COUNTY
SOUTH CAROLINA**

No.	Date	Revision

Sheet Title:
DRAINAGE PROFILES AND DETAILS

Drawn by: TB
Designed by: TB
Checked by: TB
Scale: AS SHOWN
Project No. 22116
Date: 5/10/2022
Drawing No. 5
C4









720 OLD CHEROKEE ROAD
LEXINGTON, SOUTH CAROLINA 29072
803-957-7027 FAX 877-728-0808

**CARGILL MEAT SOLUTIONS
NEW TRUCK AREA & BUILDING ADDITION**
 LEXINGTON COUNTY
SOUTH CAROLINA

No.	Date	Revision

Sheet Title:	
DRAINAGE DETAILS	
Drawn by:	TB
Designed by:	TB
Checked by:	TB
Scale:	AS SHOWN
Project No.:	22116
Date:	5/10/2022

C5



- NOTES:**
- CONTRACTOR SHALL INSPECT BAFFLES AT LEAST ONCE A WEEK AND AFTER EACH RAINFALL. MAKE ANY REQUIRED REPAIRS IMMEDIATELY.
 - CONTRACTOR TO REMOVE SEDIMENT DEPOSITS WHEN IT REACHES HALF FULL TO PROVIDE ADEQUATE STORAGE VOLUME FOR THE NEXT RAIN EVENT AND TO REDUCE PRESSURE ON THE BAFFLES. SEDIMENT DEPTH SHOULD NEVER EXCEED HALF THE STORAGE DEPTH.
 - AFTER CONTRIBUTING DRAINAGE AREA HAS BEEN PROPERLY STABILIZED, REMOVE ALL BAFFLE MATERIALS AND UNSTABLE SEDIMENT DEPOSITS, BRING THE AREA TO GRADE, AND STABILIZE IT.

- NOTES:**
- ALL CONCRETE SHALL BE 3,000 PSI.
 - ENDS OF ALL PIPES SHALL BE FLUSH WITH INSIDE WALL.
 - ALL STEEL BARS SHALL BE PLACED 1-1/2" CLEAR FROM BOTTOM AND SIDES OF SLAB.
 - FOR PIPES UP TO 24" I.D. USE 3'-0" x 3'-0" BOX.
 - FOR PIPES OVER 24" I.D. BOX INSIDE DIMENSIONS SHALL BE PIPE O.D. + 6" EACH SIDE OF PIPE.
 - ALL STEPS SHALL PROTRUDE 4" FROM THE INSIDE FACE OF STRUCTURE WALL.
 - CONCRETE BRICK WALLS SHALL HAVE A 1/4" MORTAR COAT ON INSIDE SURFACE.
 - WALL THICKNESS IS TO BE 12" IF BOX DEPTH EXCEEDS 12'-0".
 - ALL MATERIALS AND CONSTRUCTION ARE TO COMPLY WITH SECTION 720 OF THE SCDOT STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.
 - REINFORCED CONCRETE MAY BE SUBSTITUTED FOR BRICK WALLS. REINFORCING TO BE #4 BARS @ 12" E.W.

- GENERAL NOTES:**
- DROP INLET MAY BE CONSTRUCTED OF CLASS 'A' CONCRETE, 8" BRICK, OR PRECAST CONCRETE.
 - CONCRETE INLETS SHALL HAVE 6" THICK WALLS AND 4" THICK BOTTOM.
 - BRICK INLETS SHALL HAVE 8" THICK WALLS AND 6" THICK BOTTOM SLAB.
 - MINIMUM INSIDE DIMENSIONS SHALL BE 3'-0" x 3'-0" FOR PIPES 24" I.D. AND LESS. FOR PIPES 30" I.D. AND GREATER MINIMUM INSIDE DIMENSIONS SHALL BE PIPE O.D. + 6" EACH SIDE OF PIPE.
 - AFTER FRAME AND GRATE ARE SET, FINAL 4" CLASS 'A' CONCRETE IS TO BE POURED FLUSH WITH THE OUTSIDE EDGE OF THE DROP INLET ON ALL SIDES.
 - METAL STEPS ARE TO BE SET IN WALL IF INLET DEPTH EXCEEDS 4'-6". SAID STEPS TO CONFORM TO S.C.D.H.P.T. DRAWING No. 719-1.
 - CORBEL BRICK WORK AS REQUIRED ON BRICK INLETS TO PROVIDE 4" MINIMUM CLEARANCE BETWEEN PIPE AND BRICK WALLS.
 - ENDS OF ALL PIPES SHALL BE FLUSH WITH INSIDE WALL OF INLET.
 - CONCRETE INLETS CONSTRUCTED ON SANDY SOIL SHALL HAVE 1/2" REINFORCING STEEL PLACED 8" O/C HORIZONTAL AND 14" O/C VERTICAL WITH 2" CLEARANCE FROM INSIDE FACE OF CONCRETE.